8 th Ave and 12 th Street Paving			
RFQ Identification Number:			and Market
ToFM-PW-RFQ-2025-011		F	ort Macleod
Administered by:	Brennan Orr, Director of Operations	Initiation Date:	2025.05.07
Contact:	operations@fortmacleod.com,	Close Date:	
	(403) 553-4425		2025.05.23

1 Introduction

The Town of Fort Macleod is requesting quotations from individuals or contractors with experience in road construction to pave the gravel section of a municipal road in Fort Macleod.

The Town encourages contractors to seek efficiencies by combining several road and asphalt jobs which will be announced concurrently. Opportunities to reduce mob, waste, and scheduling costs will be considered when awarding individual contracts.

- Interested parties must have proof of liability insurance, registered with WCB Alberta, hold a valid Town of Fort Macleod Business License, and detailed information on criteria for payment
- 2. The Town of Fort Macleod reserves the right to reject any and all bids
- 3. The Town of Fort Macleod has the right to select the proposal that best satisfies its interests and not necessarily on the basis of price or any other single factor
- 4. The town will not be liable for any additional work or damages directly attributed to neglect or poor workmanship of the prime contractor or any of their subcontractors

2 Scope

The Town of Fort Macleod will require the successful party to:

- Self-Assess the location and condition of the current road, and suggest any
 efficiency for the course of work
- Coordinate all traffic controls, road closures, and communicate with the town for resident awareness
- Manage all equipment as well as worker safety and incident investigations
- Prepare base structure for asphalt according to City of Lethbridge Design Standards for an Industrial Road
- Manage all dust controls during construction activities

ToFM-PW-RFQ-2025-011	8 th Ave and 12 th Street Paving	Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	20, 410 20 th St

- Adjustments to heights of manholes and/or main valves present on this stretch of road
- Install asphalt according to City of Lethbridge Design Standards for an Industrial Road
- Mob and Demob comment on efficiencies with other open tenders

3 Schedule

The Town of Fort Macleod will require an estimated schedule of procurement, execution and finishing. The successful party will coordinate:

- Site inspections to ensure understanding of the details of the bid
- Highlight any material deliveries delays
- Efficient coordination of multiple potential tenders in town
- Traffic controls
- Work Execution

4 Details

4.1 Scope:

- Traffic and dust control
- Surface area is ~8m wide roadway on 8th Ave starting just south of 12th street down to 9th Street
 - o ~8m wide X 260m long
 - o ~2,100m²
- Preparation of the base
 - o Controlling the profile to shed water to east and west ditches, 2% slope
 - Adding material as needed to meet City of Lethbridge minimum roadway paving requirements for an Industrial Road
 - Final grade and compaction
- Tie-in to 12th Street asphalt
- Adjustments and risers to be added to manholes and main valves as required
 - Four main valves
 - o Three manholes

ToFM-PW-RFQ-2025-011	8 th Ave and 12 th Street Paving	Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	20, 410 20 th St

- Installation of asphalt
 - Asphalt must meet City of Lethbridge minimum roadway standards for an Industrial Road
 - 100mm Type II Asphalt Base Course
 - 60mm Type I Asphalt Surface
- Cleanup and Demob

4.2 City of Lethbridge Minimum Roadway Pavement Requirements:

6.16 MINIMUM ROADWAY PAVEMENT REQUIREMENTS

The following table outlines the minimum materials required for the pavement structures of roadways for the City of Lethbridge:

Table 6.16.1 MINIMUM REQUIREMENTS FOR ROADWAY PAVEMENT STRUCTURES (mm)

Material	Maximum Aggregate Size (mm)	Arterial	Super Collector	Major & Minor Collector	Local	Industrial	Lane	Local Industrial*
Type I Asphalt Surface	16	60	60	60		60		50
Type II Asphalt Base Course	25	100	80	60		100		50
Type III Asphalt Surface	16				90		80	
Granular Base Course	25	100	100	100	250	100	200	250
Granular Subbase	75	350	350	150		250		
Subgrade		300	300	300	300	300	300	

^{*} Use of the Local Industrial road structure requires approval by the Transportation business unit on a case-by-case basis.

ToFM-PW-RFQ-2025-011	8 th Ave and 12 th Street Paving	Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	20, 410 20 th St

4.3 Location / Area:

Figure 1



Note: Orange-highlighted rectangle designating area of work

ToFM-PW-RFQ-2025-011	8 th Ave and 12 th Street Paving	Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	0, 410 20 th St

Figure 2



Note: GIS estimation of designated road surface area, to be confirmed by contractor through visit to site

ToFM-PW-RFQ-2025-011 8 th Ave and 12 th Street Paving		Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	20, 410 20 th St

Figure 3



Note: Conceptual image of asphalt and curb placement, to be confirmed by contractor through visit to site

ToFM-PW-RFQ-2025-011	8 th Ave and 12 th Street Paving	Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	0, 410 20 th St

5 Submission Requirements

Please forward your price quotations to the Town of Fort Macleod

CLOSE DATE: Friday, May 23rd 2025, at 4 pm

Electronically (Preferred)

Email Address: operations@fortmacleod.com

Subject Line: Include the RFQ Identification Number and Title

Attention: Brennan Orr, Director of Operations

Hand delivered

Address: 410-20th St. Fort Macleod, AB T0L 0Z0

Standard Mail

Attention: Brennan Orr

Town of Fort Macleod

Box 1420

Fort Macleod, AB T0L 0Z0

ToFM-PW-RFQ-2025-011	8 th Ave and 12 th Street Paving	Close Date	2025.05.23
operations@fortmacleod.com	Brennan Orr, Director of Operations	PO Box 142	.0, 410 20 th St